


PROPOSED SITE IMPROVEMENTS


THE CONSERVATIVE SYNAGOGUE
28 HILLSPPOINT ROAD
WESTPORT, CONNECTICUT

SITE DEVELOPMENT PLAN DRAWINGS

ZONE: AA/AAA



LOCATION MAP
SCALE: 1"=800'



PLAN
SCALE: 1"=80'

DRAWING LIST

SHEET #	DRAWING TITLE
01-01	COVER SHEET
11-01	SITE DEVELOPMENT PLAN
12-01	GRADING, DRAINAGE AND UTILITY PLAN
12-02	GRADING & DRAINAGE DETAIL - ENTRANCE
13-01	SOIL EROSION & SEDIMENT CONTROL PLAN
13-02	SOIL EROSION & SEDIMENT CONTROL NOTES & DETAILS
19-01	SITE LIGHTING PLAN
19-02	SITE LIGHTING NOTES & DETAILS
20-01	CONSTRUCTION DETAILS AND NOTES

OWNER
The Conservative Synagogue
28 Hillspoint Road
Westport, Connecticut 06880


ARCHITECT
Perkins Eastman
115 Fifth Avenue
New York, New York 10003
T: (212) 353-7650


LAND CONSULTANT
Barr Associates LLC
25 Sylvan Road South, Suite P
Westport, Connecticut 06880

LAND SURVEYOR
Leonard Surveyors, LLC
1175 Post Road East
Westport, Connecticut 06880
T: (203) 226-7861
F: (203) 454-1832

SITE ENGINEER
B&B Engineering
15 Research Drive, Suite 3
Woodbridge, Connecticut 06525
T: (203) 881-8145








- GENERAL NOTES**
- BUILDING FOOTPRINT IS BASED OFF OF DRAWINGS OBTAINED FROM THE OWNER AND/OR ARCHITECT. CONTRACTOR SHOULD REFER TO ARCHITECTURAL DRAWINGS FOR EXACT BUILDING DIMENSIONS & ACTUAL LOCATIONS OF UTILITY ENTRANCES.
 - LOCATION OF ALL UNDERGROUND UTILITIES DEPICTED HEREON ARE APPROXIMATE AND ARE BASED ON FIELD LOCATION OF VISIBLE STRUCTURES SUCH AS CATCH BASINS, MANHOLES, WATER GATES, ETC., AND COMPLYING INFORMATION FROM PLANS SUPPLIED BY THE RESPECTIVE UTILITY COMPANIES AND GOVERNMENT AGENCIES. ALL CONTRACTORS ARE REQUIRED BY STATE REGULATIONS TO CONTACT CALL-BEFORE-YOU-DIG AT 1-800-922-4455 FOR LOCATION AND STAKEOUT OF UTILITIES PRIOR TO ANY EXCAVATION.
 - IF THERE ARE ANY VARIATIONS ON THIS MAP WITH WHAT IS FOUND OR DESIRED IN THE FIELD, THE CONTRACTOR SHALL CONTACT AND NOTIFY THE SITE ENGINEER IMMEDIATELY PRIOR TO COMMENCING THE RELATED WORK TO DETERMINE THE CORRECT COURSE OF ACTION.
 - B&B ENGINEERING, LLC MAKES NO GUARANTEE WITH THIS PLAN UNLESS B&B INSPECTS ALL ASPECTS OF CONSTRUCTION.
 - MAP REFERENCES:
 - BOUNDARY AND TOPOGRAPHIC INFORMATION OBTAINED FROM A MAP ENTITLED "EXISTING CONDITIONS PLOT PLAN PREPARED FOR CONSERVATIVE SYNAGOGUE, INC.; 28 HILLSPOINT ROAD, WESTPORT, CONNECTICUT" DATED: SEPTEMBER 7, 2016, REVISED: APRIL 17, 2017, PREPARED BY LEONARD SURVEYORS, LLC., WESTPORT, CONNECTICUT.
 - SOIL TEST DATA OBTAINED FROM A PROGRESS PRINT PLAN ENTITLED "SITE DEVELOPMENT PLANS FOR PROPOSED ADDITIONS; SITE LAYOUT PLAN AND NOTES" DATED: 5/23/17, PREPARED BY RICHARD BENNETT AND ASSOCIATES, LLC, WESTPORT, CT

N/F
KATHLEEN NUSBAUM

No.	Date	REVISION DESCRIPTION
1.	1/17/2020	PLANNING & ZONING SUBMISSION



B&B ENGINEERING

15 Research Drive
Suite 3
Woodbridge, CT 06626
P: (203) 881-8145
www.bbangs.com

Land Surveying, Professional Engineering & Land Use Consultants

GRADING, DRAINAGE AND UTILITY PLAN
OF
28 HILLSPOINT ROAD
WESTPORT, CONNECTICUT
PREPARED FOR
THE CONSERVATIVE SYNAGOGUE
30 HILLSPOINT ROAD
WESTPORT, CONNECTICUT 06880

TO THE BEST OF MY KNOWLEDGE AND BELIEF THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.	Date 1/10/2020
	Scale 1"=30'
	Job No. 973
	Drawing No. 12-01

THIS DOCUMENT, THE IDEAS AND DESIGN INCORPORATED HEREON IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND THE PROPERTY OF B&B ENGINEERING, LLC AND IS NOT TO BE REPRODUCED OR USED IN WHOLE OR IN PART FOR ANY EXTENSION OF THIS PROJECT OR FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF B&B ENGINEERING, LLC.

BRYAN P. NESTERIK, CT, P.E., L.S. 23556

LEGEND

- C.H.D. Monument
- Mon. Iron Pin to be Set
- Conc. Monument to be Set
- Iron Pipe
- I.P. Iron Pin
- D.H. Drill Hole
- Pile of Stones
- F.P. Fence Post
- Fnd. Found
- n/f Now or Formerly
- Property Line
- Property Line (adjoining)
- Building Setback Line
- Easement Line
- Centerline
- Ledge or Boulders
- Earth or gravel fill
- Existing Spot Elevation
- Proposed Spot Elevation
- Invert Elevation of Pipe
- Conn. Hwy. Dept. Monument
- W Water main (existing)
- W Water main (proposed)
- Hydrant
- WS Water service lateral
- G Gas main (existing)
- G Gas main (proposed)
- SS Sanitary sewer lateral
- S Sanitary Sewer Main (existing)
- S Sanitary Sewer Main (proposed)
- Stone Wall
- Barbed Wire Fence
- Fence
- Utility Pole
- Existing Manhole
- Proposed Manhole
- Existing Catch Basin/Pipe
- Proposed Storm Pipe
- Proposed Catch Basin
- Building (existing)
- Water gate valve
- Gas gate valve
- Swamp or Wetlands
- Watercourse
- Existing Contours
- Proposed Contours
- Reinforced Concrete Pipe
- Corrugated Metal Pipe
- Percolation Test Location
- Deep Test Pit Location
- Stone Retaining Wall
- Retaining Wall
- Wetland Limit
- Wetland Flag Number
- Wetland Setback
- Benchmark
- Silt Fence
- Well (existing)
- Well (proposed)
- Anti-Mud Tracking Pad
- Evergreen Tree
- Deciduous Tree
- Swamp or Wetlands
- Watercourse
- Existing Contours
- Proposed Contours
- Reinforced Concrete Pipe
- Corrugated Metal Pipe
- Percolation Test Location
- Deep Test Pit Location
- Stone Retaining Wall
- Retaining Wall
- Wetland Limit
- Wetland Flag Number
- Wetland Setback
- Benchmark
- Silt Fence
- Well (existing)
- Well (proposed)
- Anti-Mud Tracking Pad

EXCAVATION STATISTICS

FILL AND EXCAVATION VOLUME	MAXIMUM ALLOWED	PROVIDED
MAX. FILL OR EXCAVATION HEIGHT	10'	3.6'
		1,800 CY CUT
		1,092 CY FILL
		TOTAL = 2,892 CY

1. THESE GUIDELINES SHALL APPLY TO ALL WORK CONSIDERING OF ANY AND ALL TEMPORARY AND/OR PERMANENT MEASURES TO CONTROL WATER POLLUTION AND SOIL EROSION AS WELL AS THE PROTECTION OF WETLANDS AND WATERBODIES.
2. ALL CONSTRUCTION ACTIVITIES SHALL PROCEED SO THAT POLLUTION OF ANY WETLANDS, WATERCOURSES, WATERBODY, AND OR CARRYING WATER, ETC. DOES NOT OCCUR OR IS MINIMIZED. THE CONTRACTOR SHALL TAKE PREVENTATIVE MEASURES TO PREVENT MATERIALS EXPOSED BY CONSTRUCTION METHODS AND IMMEDIATELY PROVIDE PERMANENT AND TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF WETLANDS, WATERCOURSES, WATERBODIES AND TO PREVENT INJURY AS POSSIBLE EROSION ON THE SITE.
3. CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN THE "GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" (2002) BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION.

IMPLEMENTATION NOTES

- THE EROSION AND SEDIMENTATION CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO CONSTRUCTION WHENEVER POSSIBLE. ALL CONTROL MEASURES ARE TO BE MAINTAINED IN AN ACTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. ADDITIONAL MEASURES ARE TO BE INSTALLED IF NECESSARY OR REQUIRED DURING CONSTRUCTION PERIOD.
- LAND DISTURBANCE SHALL BE KEPT TO A MINIMUM. RESTABILIZATION TO BE SCHEDULED AS SOON AS PRACTICAL.
- POST AND FABRIC SLOPING BARRIERS SHALL BE INSTALLED AT THE TOE OF ALL CRITICAL EROSION SLOPES. SLOPE SILL FENCES AND BARRIERS SHALL BE CLEANED OR REPLACED WHEN THEY HAVE REACHED ONE-THIRD THE HEIGHT OF THE FENCE.
- ALL STORM DRAINAGE OUTLETS MUST BE STABILIZED, AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.
- SEDIMENT TRAPS, IF APPLICABLE, MUST BE CLEANED WHEN CAPACITY HAS BEEN REDUCED BY AN AVERAGE OF 2' OVER ITS TOTAL AREA OR TO 80% OF ITS DESIGN VOLUMES, WHICHEVER OCCURS FIRST.
- SEDIMENT REMOVED FROM THE CONTROL STRUCTURES SHALL BE DISPOSED OF IN A MANNER CONSISTENT WITH THE INTENT OF THE PLAN AND IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
- FILL MATERIAL SHALL BE FREE FROM DEBRIS PERMEABLE OR COMBUSTIBLE MATERIAL, AND FROZEN WEATHER OR ROCKS LARGER THAN 6 INCHES IN MAXIMUM DIMENSION. FILL SHALL BE LAYED IN MAXIMUM 12 INCH LOOSE LIFTS AND COMPACTED TO WITHIN 90% OF THE MODIFIED PROCTOR TEST RESULT.
- PAVEMENT BASE COURSE MUST BE PLACED IN ALL PROPOSED PAVEMENT AREAS UPON COMPLETION OF FINAL GRADING.
- PERMANENT LANDSCAPED AREAS SHALL BE SEEDDED OR SOODED ON ALL EXPOSED AREAS IMMEDIATELY AFTER FINAL GRADING. MUCH AS NECESSARY FOR SEED PROTECTION AND ESTABLISHMENT. LIME AND FERTILIZER PRIOR TO PERMANENT SEEDING.
- TOPSOIL PREPARATION:
 - 9.1.1. TOPSOIL SHOULD BE A MINIMUM OF FOUR INCHES DEEP (COMPACTED) BEFORE SEEDING.
 - 9.1.2. HAVE TOPSOIL TESTED FOR PH, ADD LIME AS NECESSARY TO ACHIEVE PH OF 6.5. ADD FERTILIZER AT THE RATE OF 100 POUNDS PER ACRE OR SEVEN POUNDS PER 4,000 SQUARE FEET USING 10-20-10 OR EQUIVALENT. IN ADDITION, 300 LBS OF 38-0-0 PER ACRE OF SLOW RELEASE NITROGEN MAY BE USED IN LIEU OF TOP DRESSING.
 - 9.1.3. WORK LIME AND FERTILIZER INTO SOIL AS NEARLY AS PRACTICAL, TO A DEPTH OF 4 INCHES. WHENEVER AVAILABLE, A SMOOTH DRAP OR OTHER SUITABLE EQUIPMENT. THE INITIAL HARROWING OR DISING OPERATION SHOULD BE ON THE REMOVED TOPSOIL. CONTINUE ADDING FERTILIZER UNTIL THE COARSE SANDS BECOMING BE READY TO FILL THE SEED BED WHEN FEASIBLE.
 - 9.1.4. GENERATE FROM THE SURFACE ALL STONES ONE INCH OR LARGER IN ANY DIMENSION, REMOVED FROM THE AREA AND OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, LUMP, OR OTHER UNSUITABLE MATERIAL.
 - 9.1.5. INSPECT SEED BED BEFORE SEEDING. IF TRAFFIC HAS LEFT SOIL COMPACT, THE AREA MUST BE RESEED AND RECOMPACTED ABOVE.
 - 9.2. SEED MIXTURE (APPLY AT A RATE OF 200 POUNDS/ACRE):
 - 9.2.1. 10% KENTUCKY BLUEGRASS - BARNUM MIX
 - 9.2.2. 20% PERENNIAL WHEAT - 20% COMPACTED ABOVE
 - 9.2.3. 70% TURF TYPE TALL FESCUE
- THE CONTRACTOR/OWNER IS RESPONSIBLE FOR ALL PAVED ROADWAYS ON AND OFF SITE AND MUST ENSURE THE SITE IS FREE OF SITE GENERATED SEDIMENT AT ALL TIMES. DUST SHALL BE CONTROLLED BY SPRINKLING OR ANOTHER APPROVED METHOD.
- ALL EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSPECTED ON A DAILY BASIS AND CLEANED IMMEDIATELY AFTER EACH STORM.
- WHERE Dewatering is necessary, there shall not be a discharge directly into wetlands or watercourses. Proper methods and devices shall be utilized to ensure the permittee complies with the discharge as pumping water into a temporary sedimentation structure or bowl, providing surge protection at the inlet and outlet, and the pumping operation shall be controlled to prevent the discharge to minimize and retain the suspended solids; if pumping operation causes turbidity problems, the operation shall cease until feasible means of controlling turbidity are determined.
- THE RESPONSIBILITY FOR IMPLEMENTING THE EROSION AND SEDIMENT CONTROL PLAN, INFORMING ALL CONCERNED OF THE REQUIREMENT OF THE PLAN, NOTIFYING THE PLANNING AND ZONING COMMISSION, ITS DESIGNATED REPRESENTATIVE OF ANY TRANSFER OF REAL ESTATE, AND PROVIDING A COPY OF THE PLAN IS RECEIVED BY ANY SUCCESSOR IN INTEREST TO THE TITLE OF THE LAND OR ANY PORTION THEREOF IS ASSIGNED TO THE OWNER OF RECORD.
- ANY CONVEYANCE OF THIS PROJECT PRIOR TO ITS COMPLETION, WILL TRANSFER FULL RESPONSIBILITY FOR COMPLIANCE WITH THE CERTIFIED PLAN TO ANY SUBSEQUENT OWNERS.

[illegible]

THIS DOCUMENT, THE IDEAS, AND DESIGN INCORPORATED
HEREON IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND
THE PROPERTY OF B&B ENGINEERING, L.L.C. AND IS NOT TO
BE REPRODUCED OR USED IN WHOLE OR IN PART FOR ANY
EXTENSION OF THIS PROJECT OR FOR ANY OTHER PROJECT
WITHOUT THE WRITTEN AUTHORIZATION OF B&B ENGINEERING, L.L.C.

[illegible]

28 HILLSPPOINT ROAD, WESTPORT, CT


SEDIMENTATION & SOIL EROSION NARRATIVE

- PROPOSED DEVELOPMENT
- CONSTRUCTION WILL INCLUDE DEMOLITION, FILL PLACEMENT, EXCAVATION, CURBING, PAVING, LANDSCAPING, AND BUILDING CONSTRUCTION. ALL DEMOLITION DEBRIS AND SOIL REMOVAL RELATED TO CONSTRUCTION SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL LAWS GOVERNING SUCH ACTIVITIES.
 - THE DETAILED SEDIMENTATION AND SOIL EROSION MEASURES ARE SHOWN ON THE SOIL EROSION AND SEDIMENT CONTROL PLAN (DRAWING # 13-01). THE PROPOSED MEASURES HAVE BEEN DESIGNED TO PREVENT THE MIGRATION OF SOIL SEDIMENT FROM THE SITE.
- SOIL EROSION AND SEDIMENT CONTROL NOTES
- THE SOIL EROSION AND SEDIMENT CONTROL PLAN, AS WELL AS THE INSPECTION & MAINTENANCE PROCEDURES ARE THOROUGHLY OUTLINED ON DRAWING # 13-01. PREPARED FOR THE PROJECT BY BAS. THE CONTRACTOR IS OBLIGATED TO REVIEW, UNDERSTAND, AND AGREE TO ALL THE REQUIREMENTS OF THE PLAN AS WELL AS THE FOLLOWING NOTES.
 - THE SOIL EROSION AND SEDIMENT CONTROL PRACTICES MUST BE APPROVED & INSTALLED IN ACCORDANCE WITH THE LOCAL GOVERNING AUTHORITY AND THE PROVISIONS SET FORTH IN THE "GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" (2002) BY THE STATE OF CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION.
 - EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSTALLED PRIOR TO START OF DEMOLITION AND CONSTRUCTION, AND DISTURBANCE OF SITE CONTRIBUTORY DRAINAGE AREAS. THE OWNER OR ITS CONTRACTOR SHALL INSPECT, REPAIR AND REMOVE ALL SOIL EROSION AND SEDIMENT CONTROL DEVICES, AS INDICATED HEREIN.
 - DISPOSAL OF COLLECTED SEDIMENT SHALL BE MADE TO AREA DESIGNATED BY THE OWNER'S SOIL ENGINEER.
 - FILTER FABRIC/SILT FENCE SHALL BE INSTALLED ALONG THE TOE OF ALL CRITICAL CUT AND FILL SLOPES.
 - ALL TOPSOIL NOT TO BE USED FOR FINAL GRADING/LANDSCAPED AREAS SHALL BE REMOVED FROM THE SITE IMMEDIATELY, IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL LAW. ALL TOPSOIL TO BE USED IN LANDSCAPED AREAS SHALL BE STORED/STOCKPILED IN ACCORDANCE WITH APPLICABLE STATE AND LOCAL LAW STANDARDS.
 - ALL AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL.
 - SEDIMENT DISPOSAL AREAS AND TOPSOIL STOCKPILES NOT SCHEDULED FOR SOIL EROSION AND SEDIMENT CONTROL ACTIVITIES WITHIN THIRTY (30) DAYS OF DISTURBANCE SHALL BE STABILIZED AS FOLLOWS:
 - GROUND LIMESTONE AT A RATE OF 135 LBS. PER 1,000 SF.
 - FERTILIZER AT A RATE OF 14 LBS. PER 1,000 SF USING A 10-20-10 ANALYSIS OR AN EQUIVALENT.
 - ANNUAL RYE GRASS SEEDING APPLIED AT A RATE OF NOT LESS THAN 1 LB. PER 1,000 SF.
 - MULCH ALL NEWLY SEEDED AREAS WITHIN 80 LBS. OF SALT HAY OR SMALL GRAIN STRAW PER 1,000 SF.
 - BETWEEN OCTOBER 15 AND MARCH 15, WHEN DISTURBED AREAS ARE SCHEDULED FOR IMMEDIATE LANDSCAPING, THEY MAY BE MULCHED AND SEEDED PER ITEM D ABOVE.
 - PAVEMENT BASE COURSE MUST BE PLACED IN ALL NEW ROADWAY AREAS UPON COMPLETION OF FINE GRADING.
 - THE CONTRACTOR IS RESPONSIBLE FOR ALL PAVED ROADWAYS ON AND OFF-SITE AND MUST BE KEPT FREE OF SITE GENERATED SEDIMENT AT ALL TIMES. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHOD.
 - ALL STORM DRAINAGE OUTLETS MUST BE STABILIZED, AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.
 - SILT FENCES AND BARRIERS MUST BE CLEANED OR REPLACED WHEN SOIL HAS REACHED ONE-THIRD THE HEIGHT OF THE FENCE.
 - SEDIMENT TRAPS MUST BE CLEANED WHEN CAPACITY HAS BEEN REDUCED BY AN AVERAGE OF 2" OF OVER ITS TOTAL AREA OR TO 25% OF ITS DESIGN VOLUMES. WHICHEVER OCCURS FIRST. ALL SEDIMENT TRAPS OR BASINS SHALL PROVIDE A MINIMUM OF 134 CF OF WATER STORAGE PER ACRE DRAINED AND SHALL BE MAINTAINED UNTIL FINAL STABILIZATION OF THE CONTRIBUTING AREA.
 - ALL EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDER DAYS AND WITHIN 24 HOURS FOLLOWING A RAINFALL EVENT WHICH PRODUCES IN EXCESS OF 0.1 INCHES.
 - ALL EXPOSED SUBSURFACES WILL BE TREATED WITH 6" OF TOPSOIL PRIOR TO FINAL STABILIZATION.
 - PERMANENT VEGETATION IS TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN TEN (10) DAYS AFTER FINAL GRADING. MULCH AS NECESSARY FOR SEED PROTECTION AND ESTABLISHMENT. LIME AND FERTILIZE PRIOR TO PERMANENT SEEDING.
 - CONTRACTOR TO INSTALL A STRAW/COCONUT FIBER BLENDED BIODEGRADABLE SOIL EROSION MATTING ON ALL PROPOSED BASIN SLOPES ONCE PERMANENT SEEDING AND PLANTING HAS BEEN COMPLETED AS OUTLINED. THE MATTING MUST BE INSTALLED AND STAPLED TO THE SLOPES PURSUANT TO THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. ANY DEVIATIONS FROM THE PROPOSED INSTALLATION SHALL BE BROUGHT TO THE ATTENTION OF THE PROJECT ENGINEER FOR REVIEW AND APPROVAL. CONTRACTOR SHALL SUBMIT A SAMPLE OF THE PROPOSED MATTING FOR REVIEW PRIOR TO INSTALLATION.
 - SOIL EROSION AND SEDIMENT CONTROL SHALL INCLUDE, BUT NOT BE LIMITED TO, OMISSIONS, ERRORS, OR FIELD OPERATIONS IMMEDIATELY AND IN ACCORDANCE WITH THE ABOVE MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE TO CORRECT ANY OMISSIONS, ERRORS, OR FIELD OPERATIONS IMMEDIATELY AND IN ACCORDANCE WITH THE GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL.
 - ANY CONVEYANCE OF THIS PROJECT, PRIOR TO ITS COMPLETION, WILL TRANSFER FULL RESPONSIBILITY FOR COMPLIANCE WITH THE CERTIFIED PLAN TO ANY SUBSEQUENT OWNERS.



21. PERMANENT
- A. LAWN AREAS – AREAS DESIGNATED AS LAWN, OR DISTURBED AREAS NOT DESIGNATED AS LAWN. ANY OTHER PLANTING SHALL BE PERMANENTLY STABILIZED BY SEEDING WITH THE FOLLOWING SEED MIXTURE AT A RATE OF 200 POUNDS/ACRE:
- 10% KENTUCKY BLUEGRASS – BARON MIX
20% PERENNIAL RYEGRASS
70% TURF TYPE TALL FESCUE
- NOTES:
- SEED AT A RATE OF 15 LBS./ACRES
 - FOR SPRING SEEDING, APPLY A NURSE CROP OF OATS AT A RATE OF 20 LB./ACRE
 - FOR FALL SEEDING, APPLY A NURSE CROP OF BARLEY AT A RATE OF 20 LBS./ACRE
 - ANY SOIL HAVING A PH OF 4 OR LESS CONTAINING IRON SULFIDES SHALL BE COVERED WITH A MINIMUM TWELVE INCHES OF SOIL HAVING A PH OF FIVE OR MORE PRIOR TO SEED BED PREPARATION.
 - LIME – THREE TONS PER ACRE, GROUND LIMESTONE INCORPORATED FOUR INCHES INTO SOIL
 - FERTILIZER – 500 LBS. PER ACRE, 10-20-10 INCORPORATED FOUR INCHES INTO SOIL.
- B. GENERAL SEEDING NOTES
- FINAL SEED MIXTURES, RATES & SEWPECIES TO BE DETERMINED BASED ON SCD REV
 - SEEDING SHALL TAKE PLACE IN THE SPRING (APRIL 1 TO JUNE 1) OR THE FALL (SEPTEMBER 1 TO OCTOBER 30)
 - ELIMINATE UNWANTED VEGETATION PRIOR TO SEEDING USING A BROAD-SPECTRUM NON-SELECTIVE HERBICIDE PER MANUFACTURER'S SPECIFICATIONS.
 - IT IS RECOMMENDED THAT CONTRACTOR INSTALL SEED MIXTURE USING A NO-TILL TRIUM-TRAX TYPE DRILL WHERE APPLICABLE
 - CONTINUOUS MOISTURE FOR 4-6 WEEKS MUST BE INSURED TO ALLOW PROPER GERMINATION.
- C. WEDD CONTROL / MAINTENANCE
- DURING THE ESTABLISHMENT YEAR, CONTRACTOR SHALL MOW SEEDING IF WEED HEIGHT EXCEEDS MEADOW MIX HEIGHT. MOW AT A HEIGHT OF 8"-10". DO NOT MOW WINTER, AS SOME OF THE INDIVIDUALS WHO WILL BE RESPONSIBLE FOR THESE INSPECTIONS, MAINTENANCE AND REPAIR ACTIVITIES, AND FILLING OUT INSPECTION AND MAINTENANCE REPORT.
 - AFTER THE FIRST GROWING SEASON, AND IF MEADOW MIX IS WELL ESTABLISHED, THE MEADOW MIX SHALL BE MOWED ANNUALLY. ANNUAL MAINTENANCE MOWING SHALL BE DONE IN LATE WINTER DURING THE MONTH OF MARCH.
 - MOW IN WETLAND AND WETLAND TRANSITION AREAS DURING DRIER SITE CONDITIONS WHEN SOIL DISTURBANCE WILL NOT OCCUR. MAINTENANCE FOR WETLAND AND WETLAND TRANSITION AREAS SHALL OCCUR DURING LATE SUMMER (JULY 15 – AUGUST 15) WHEN THE WATER TABLE IS USUALLY AT ITS LOWEST POINT OF THE YEAR. DO NOT MOW IN WETLAND OR WETLAND TRANSITION AREAS AFTER ESTABLISHMENT OF MEADOW MIX.
 - MULCHING SHALL BE DONE AT THE RATE OF SEVENTY TO NINETY POUNDS PER 1,000 SQUARE FEET WITH UNROTTED SALT HAY.
- D. LIQUID MULCH BINDERS MUST BE USED TO ANCHOR SALT HAY, HAY OR STRAY MULCHES.
- APPLICATIONS SHOULD BE HEAVIER AT EDGES WHERE WIND CATCHES THE MULCH IN VALLEYS AND AT CREATED BANKS. REMAINDER OF AREA SHOULD BE UNIFORM IN APPEARANCE.
 - USE ONE OF THE FOLLOWING: SYNTHETIC OR ORGANIC BINDERS, BINDERS SUCH AS CURASOL DCA-70, PETRO SET, TERRA TACH, HYDRO MULCH AND AEROSPRAY MAY BE USED AT RECOMMENDED RATES BY THE MANUFACTURER OF ANCHOR MULCH MATERIALS. BINDERS CONTAINING PETROLEUM PRODUCTS SHALL NOT BE USED.
- C. NOTE: ALL NAMES GIVEN ABOVE ARE REGISTERED TRADE NAMES. THIS DOES NOT CONSTITUTE A RECOMMENDATION OF THESE TO THE EXCLUSION OF OTHER PRODUCTS.
- F. FILL MATERIAL SHALL BE FREE FROM DEBRIS, PERISHABLE OR COMBUSTIBLE MATERIAL AND FROZEN OR WET EARTH OR STONES LARGER THAN THREE INCHES IN MAXIMUM DIMENSION.
- G. CONSTRUCTION AREAS SHALL BE PERIODICALLY SPRAYED WITH WATER UNTIL THE SURFACE IS WET TO CONTROL THE GENERATION OF DUST.
- H. ALL REVISIONS AFTER APPROVAL HAS BEEN GRANTED SHALL BE FORWARDED TO THE APPROPRIATE DISTRICT FOR REVIEW.
- I. THE LOCAL GOVERNING AUTHORITY SHALL RECEIVE WRITTEN NOTIFICATION SEVENTY TWO HOURS BEFORE THE START OF ANY CONSTRUCTION.
- J. SEEDING PREPARATION:
- TOPSOIL SHOULD BE A MINIMUM OF SIX INCHES DEEP (COMPACTED) BEFORE SEEDING.
 - HAVE TOPSOIL TESTED FOR PH, ADD LIME AS NECESSARY TO ACHIEVE PH OF 6.5. APPLY FERTILIZER AT A RATE OF 300 POUNDS PER ACRE OR SEVEN POUNDS PER 4,000 SQUARE FEET USING 10-20-10 OR EQUIVALENT. IN ADDITION, 300 POUNDS 38-0-0 PER ACRE OF SLOW RELEASE NITROGEN MAY BE USED IN LIEU OF TOP DRESSING.
 - WORK LIME AND FERTILIZER INTO SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF FOUR INCHES WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILL CLAY OR SILTY SOIL AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEED BED WHEREVER FEASIBLE.
 - REMOVE FROM THE SURFACE ALL STONES ONE INCH OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, PIECES OF CONCRETE, CLODS, LUMP, OR OTHER UNSUITABLE MATERIAL.
 - INSPECT SEED BED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT SOIL COMPACT, THE ARE MUST BE RELOADED AND FIRMED AS ABOVE.
- K. CONTRACTOR SHALL INSTALL A FENCED AND GATED LOCATION WITH AN IMPERVIOUS FLOOR FOR STORAGE OF HAZARDOUS MATERIALS WITH A SUPPLY OF ABSORBENT SPILL RESPONSE MATERIAL AVAILABLE.
22. INSPECTIONS/MAINTENANCE POST CONSTRUCTION
- B. INSPECTIONS SHALL INCLUDE A VISUAL ASSESSMENT OF THE CONDITION/FUNCTION OF ALL THE COMPONENTS OF THE STORMWATER MANAGEMENT SYSTEM. CONDITION OF CATCH BASINS AND MANHOLES SHOULD BE DETERMINED. INTERNAL COMPONENTS OF THE STORMWATER QUALITY CHAMBERS SHOULD BE ASSESSED AND THE VOLUME OF SEDIMENTS WITHIN THE CHAMBERS SHOULD BE DETERMINED.
- C. SEDIMENTS SHALL BE REMOVED FROM WATER QUALITY CHAMBERS WHEN 70% OF THE AVAILABLE SEDIMENT STORAGE WITHIN THE UNIT HAS BEEN BEEN CONSUMED.
- D. A WRITTEN RECORD OF INSPECTIONS/MAINTENANCE SHALL BE KEPT BY THE PROPERTY OWNER AND SHALL BE MADE AVAILABLE TO TOWN OFFICIALS UPON REQUEST.

INSPECTION & MAINTENANCE PROCEDURES DURING CONSTRUCTION

- THE FOLLOWING INSPECTION AND MAINTENANCE PRACTICES WILL BE USED TO MAINTAIN SOIL EROSION AND SEDIMENT CONTROLS AND STABILIZATION MEASURES. ALL INSPECTIONS AND MAINTENANCE OF THE SOIL EROSION CONTROL MEASURES SHALL BE PERFORMED IN ACCORDANCE WITH CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION SOIL EROSION AND SEDIMENT CONTROL GUIDELINES AND THE TOWN GUIDELINES.
- ALL CONTROL MEASURES WILL BE INSPECTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS FOLLOWING A RAINFALL EVENT WHICH PRODUCES PRECIPITATION IN EXCESS OF 0.1 INCHES.
 - ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF REPAIRS OR OTHER MEASURES ARE FOUND TO BE NECESSARY, THEY WILL BE INITIATED WITHIN 24 HOURS OF REPORT.
 - BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCE WHEN IT HAS REACHED ONE-THIRD THE HEIGHT OF THE FENCE.
 - SILT FENCES WILL BE INSPECTED FOR DEPTH OF SEDIMENT, TEARS, ETC., TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POSTS, AND TO SEE THAT THE FENCE POSTS ARE SECURELY IN THE GROUND.
 - THE SEDIMENT TRAP, IF PRESENT, WILL BE INSPECTED FOR DEPTH OF SEDIMENT AND BUILT UP SEDIMENT WILL BE REMOVED WHEN IT REACHES 25 PERCENT OF THE DESIGN CAPACITY.
 - TEMPORARY AND PERMANENT SEEDING AND ALL OTHER STABILIZATION MEASURES WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTH GROWTH.
 - A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION.
 - THE JOB SITE SUPERINTENDENT WILL BE RESPONSIBLE FOR SELECTING AND TRAINING THE INDIVIDUALS WHO WILL BE RESPONSIBLE FOR THESE INSPECTIONS, MAINTENANCE AND REPAIR ACTIVITIES, AND FILLING OUT INSPECTION AND MAINTENANCE REPORT.
 - PERSONNEL SELECTED FOR THE INSPECTION AND MAINTENANCE RESPONSIBILITIES WILL RECEIVE TRAINING FROM THE JOB SITE SUPERINTENDENT. THEY WILL BE TRAINED IN ALL THE INSPECTION AND MAINTENANCE PRACTICES NECESSARY FOR KEEPING THE EROSION AND SEDIMENT CONTROLS THAT ARE USED ONSITE IN GOOD WORKING ORDER. THEY WILL ALSO BE TRAINED IN THE COMPLETION OF INITIATION OF ACTIONS REQUIRED BY, AND THE FILING OF THE INSPECTION FORMS.
 - DISTURBED AREAS AND MATERIALS STORAGE AREAS WILL BE INSPECTED FOR EVIDENCE OF OR POTENTIAL FOR POLLUTANTS ENTERING STORMWATER SYSTEMS.
 - REPORT TO THE CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION WITHIN 24 HOURS ANY NONCOMPLIANCE WITH THE SOIL EROSION AND SEDIMENT CONTROL PLAN THAT WILL ENDANGER PUBLIC HEALTH OR THE ENVIRONMENT. FOLLOW UP WITH A WRITTEN REPORT WITHIN 5 DAYS OF THE NONCOMPLIANCE EVENT. THE FOLLOWING EVENTS REQUIRE 24 HOURS REPORTING: A) ANY UNANTICIPATED BYPASS WHICH EXCEEDS ANY EFFLUENT LIMITATION IN THE PERMIT, B) ANY UPSET WHICH EXCEEDS ANY EFFLUENT LIMITATION IN THE PERMIT, AND C) A VIOLATION OF A MAXIMUM DAILY DISCHARGE LIMITATION FOR ANY OF THE POLLUTANTS LISTED BY THE EPA IN THE PERMIT TO REPORTED WITHIN 24 HOURS. THE WRITTEN SUBMISSION MUST CONTAIN A DESCRIPTION OF THE NON-COMPLIANCE AND ITS CAUSE; THE PERIOD OF NON-COMPLIANCE, INCLUDING EXACT DATES AND TIMES; AND IF THE NON-COMPLIANCE HAS NOT BEEN CORRECTED, THE ANTICIPATED TIME IT IS EXPECTED TO CONTINUE; AND STEPS TAKEN OR PLANNED TO REDUCE, ELIMINATE, AND PREVENT REOCCURRENCE OF THE NON-COMPLIANCE.
 - RELEASE OF HAZARDOUS SUBSTANCES OR OIL IN EXCESS OF REPORTABLE QUANTITIES (AS ESTABLISHED UNDER 40 CFR 110, 40 CFR 117 AND 40 CFR 302) MUST BE REPORTED. FORM G-1 PROVIDES FURTHER DETAILS ON THE NOTIFICATION AND REPORTING PROCESS.
- CONSTRUCTION SEQUENCE
- CONTACT THE TOWN ZONING, CONSERVATION, & ENGINEERING DEPARTMENTS TO SCHEDULE A PRE-CONSTRUCTION MEETING. UPON CONCLUSION OF THIS MEETING, BEGIN MOBILIZATION OF EQUIPMENT, ASSUMING TOWN IS IN AGREEMENT.
 - ESTABLISH TEMPORARY STAGING AREA FOR ANY EQUIPMENT TO BE USED.
 - INSTALL CONSTRUCTION ENTRANCES.
 - FLAG LIMITS OF CLEARING FOR THE PROJECT.
 - INSTALL SILT FENCE.
 - CLEAR, GRUB, CHIP, OR LOG THE SITE TO THE LIMITS OF CLEARING.
 - DISPOSE OF STUMPS AND BOULDERS IN ACCORDANCE WITH TOWN AND STATE REGULATIONS.
 - REMOVE AND STOCKPILE EXISTING TOPSOIL. SURROUND STOCKPILE WITH SILT FEN. IF NEEDED, SEED STOCKPILE SHOULD THE SEASONAL TIMING AND LOCATION REQUIRE.
 - INSTALL PERMANENT STORM DRAINAGE STRUCTURES.
 - INSTALL UNDERGROUND UTILITIES.
 - ROUGH GRADE PARKING LOT AND DRIVEWAY AREAS. INSTALL ASPHALT BINDER COURSE.
 - UTILIZE PARKING AREA FOR PARKING AND STAGING AREA.
 - BEGIN BUILDING CONSTRUCTION.
 - UPON COMPLETION OF BUILDING ADDITION, INSTALL TOPSOIL AND LANDSCAPING. FINAL GRADE AND STABILIZE ALL AREAS THROUGHOUT CONSTRUCTION.
 - INSTALL ASPHALT FINAL COURSE ON PARKING AREAS.
 - STRIP PARKING LOTS.
 - REMOVE DEBRIS AND SOIL EROSION MEASURES WHEN APPROPRIATE.



EROSION PROTECTION DEVICES



15 Research Drive
Suite 3
Woodbridge, CT 06625
P: (203) 881-8145
www.jobengs.com

Land Surveying, Professional Engineering & Land Use Consultants

SOIL EROSION AND SEDIMENT CONTROL NOTES & DETAILS
OF
28 HILLSPPOINT ROAD
WESTPORT, CONNECTICUT
PREPARED FOR
THE CONSERVATIVE SYNAGOGUE
30 HILLSPPOINT ROAD
WESTPORT, CONNECTICUT 06880


TO THE BEST OF MY KNOWLEDGE AND BELIEF THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

Date 1/10/2020
Scale 1"=30'
Job No. 973
Drawing No. 13-02

BRYAN F. NESTERAK, CT. P.E./L.S. 23556




28 HILLSPPOINT ROAD, WESTPORT, CT




LEGEND	
0.7	PROPOSED FOOTCANDLES
0.8	
0.9	
1.0	
1.1	
1.2	
1.3	
1.4	
1.5	
1.6	
1.7	
1.8	
1.9	
2.0	
2.1	
2.2	
2.3	
2.4	
2.5	
2.6	
2.7	
2.8	
2.9	
3.0	
3.1	
3.2	
3.3	
3.4	
3.5	
3.6	
3.7	
3.8	
3.9	
4.0	
4.1	
4.2	
4.3	
4.4	
4.5	
4.6	
4.7	
4.8	
4.9	
5.0	
5.1	
5.2	
5.3	
5.4	
5.5	
5.6	
5.7	
5.8	
5.9	
6.0	
6.1	
6.2	
6.3	
6.4	
6.5	
6.6	
6.7	
6.8	
6.9	
7.0	
7.1	
7.2	
7.3	
7.4	
7.5	
7.6	
7.7	
7.8	
7.9	
8.0	
8.1	
8.2	
8.3	
8.4	
8.5	
8.6	
8.7	
8.8	
8.9	
9.0	
9.1	
9.2	
9.3	
9.4	
9.5	
9.6	
9.7	
9.8	
9.9	
10.0	
10.1	
10.2	
10.3	
10.4	
10.5	
10.6	
10.7	
10.8	
10.9	
11.0	
11.1	
11.2	
11.3	
11.4	
11.5	
11.6	
11.7	
11.8	
11.9	
12.0	
12.1	
12.2	
12.3	
12.4	
12.5	
12.6	
12.7	
12.8	
12.9	
13.0	
13.1	
13.2	
13.3	
13.4	
13.5	
13.6	
13.7	
13.8	
13.9	
14.0	
14.1	
14.2	
14.3	
14.4	
14.5	
14.6	
14.7	
14.8	
14.9	
15.0	
15.1	
15.2	
15.3	
15.4	
15.5	
15.6	
15.7	
15.8	
15.9	
16.0	
16.1	
16.2	
16.3	
16.4	
16.5	
16.6	
16.7	
16.8	
16.9	
17.0	
17.1	
17.2	
17.3	
17.4	
17.5	
17.6	
17.7	
17.8	
17.9	
18.0	
18.1	
18.2	
18.3	
18.4	
18.5	
18.6	
18.7	
18.8	
18.9	
19.0	
19.1	
19.2	
19.3	
19.4	
19.5	
19.6	
19.7	
19.8	
19.9	
20.0	
20.1	
20.2	
20.3	
20.4	
20.5	
20.6	
20.7	
20.8	
20.9	
21.0	
21.1	
21.2	
21.3	
21.4	
21.5	
21.6	
21.7	
21.8	
21.9	
22.0	
22.1	
22.2	
22.3	
22.4	
22.5	
22.6	
22.7	
22.8	
22.9	
23.0	
23.1	
23.2	
23.3	
23.4	
23.5	
23.6	
23.7	
23.8	
23.9	
24.0	
24.1	
24.2	
24.3	
24.4	
24.5	
24.6	
24.7	
24.8	
24.9	
25.0	
25.1	
25.2	
25.3	
25.4	
25.5	
25.6	
25.7	
25.8	
25.9	
26.0	
26.1	
26.2	
26.3	
26.4	
26.5	
26.6	
26.7	
26.8	
26.9	
27.0	
27.1	
27.2	
27.3	
27.4	
27.5	
27.6	
27.7	
27.8	
27.9	
28.0	
28.1	
28.2	
28.3	
28.4	
28.5	
28.6	
28.7	
28.8	
28.9	
29.0	
29.1	
29.2	
29.3	
29.4	
29.5	
29.6	
29.7	
29.8	
29.9	
30.0	
30.1	
30.2	
30.3	
30.4	
30.5	
30.6	
30.7	
30.8	
30.9	
31.0	
31.1	
31.2	
31.3	
31.4	
31.5	
31.6	
31.7	
31.8	
31.9	
32.0	
32.1	
32.2	
32.3	
32.4	
32.5	
32.6	
32.7	
32.8	
32.9	
33.0	
33.1	
33.2	
33.3	
33.4	
33.5	
33.6	
33.7	
33.8	
33.9	
34.0	
34.1	
34.2	
34.3	
34.4	
34.5	
34.6	
34.7	
34.8	
34.9	
35.0	
35.1	
35.2	
35.3	
35.4	
35.5	
35.6	
35.7	
35.8	
35.9	
36.0	
36.1	
36.2	
36.3	
36.4	
36.5	
36.6	
36.7	
36.8	
36.9	
37.0	
37.1	
37.2	
37.3	
37.4	
37.5	
37.6	
37.7	
37.8	
37.9	
38.0	
38.1	
38.2	
38.3	
38.4	
38.5	
38.6	
38.7	
38.8	
38.9	
39.0	
39.1	
39.2	
39.3	
39.4	
39.5	
39.6	
39.7	
39.8	
39.9	
40.0	
40.1	
40.2	
40.3	
40.4	
40.5	
40.6	
40.7	
40.8	
40.9	
41.0	
41.1	
41.2	
41.3	
41.4	
41.5	
41.6	
41.7	
41.8	
41.9	
42.0	
42.1	
42.2	
42.3	
42.4	
42.5	
42.6	
42.7	
42.8	
42.9	
43.0	
43.1	
43.2	
43.3	
43.4	
43.5	
43.6	
43.7	
43.8	
43.9	
44.0	
44.1	
44.2	
44.3	
44.4	
44.5	
44.6	
44.7	
44.8	
44.9	
45.0	
45.1	
45.2	
45.3	
45.4	
45.5	
45.6	
45.7	
45.8	
45.9	
46.0	
46.1	
46.2	
46.3	
46.4	
46.5	
46.6	
46.7	
46.8	
46.9	
47.0	
47.1	
47.2	
47.3	
47.4	
47.5	
47.6	
47.7	
47.8	
47.9	
48.0	
48.1	
48.2	
48.3	
48.4	
48.5	
48.6	
48.7	
48.8	
48.9	
49.0	
49.1	
49.2	
49.3	
49.4	
49.5	
49.6	
49.7	
49.8	
49.9	
50.0	
50.1	
50.2	
50.3	
50.4	
50.5	
50.6	
50.7	
50.8	
50.9	
51.0	
51.1	
51.2	
51.3	
51.4	
51.5	
51.6	
51.7	
51.8	
51.9	
52.0	
52.1	
52.2	
52.3	
52.4	
52.5	
52.6	
52.7	
52.8	
52.9	
53.0	
53.1	
53.2	
53.3	
53.4	
53.5	
53.6	
53.7	
53.8	
53.9	
54.0	
54.1	
54.2	
54.3	
54.4	
54.5	
54.6	
54.7	
54.8	
54.9	
55.0	
55.1	
55.2	
55.3	
55.4	
55.5	
55.6	
55.7	
55.8	
55.9	
56.0	
56.1	
56.2	
56.3	
56.4	
56.5	
56.6	
56.7	
56.8	
56.9	
57.0	
57.1	
57.2	
57.3	
57.4	
57.5	
57.6	
57.7	
57.8	
57.9	
58.0	
58.1	
58.2	
58.3	
58.4	
58.5	
58.6	
58.7	
58.8	
58.9	
59.0	
59.1	
59.2	
59.3	
59.4	
59.5	
59.6	
59.7	
59.8	
59.9	
60.0	
60.1	
60.2	
60.3	
60.4	
60.5	
60.6	
60.7	
60.8	
60.9	
61.0	
61.1	
61.2	
61.3	
61.4	
61.5	
61.6	
61.7	
61.8	
61.9	
62.0	
62.1	
62.2	
62.3	
62.4	
62.5	
62.6	
62.7	
62.8	
62.9	
63.0	
63.1	
63.2	
63.3	
63.4	
63.5	
63.6	
63.7	
63.8	
63.9	
64.0	
64.1	
64.2	
64.3	
64.4	
64.5	
64.6	
64.7	
64.8	
64.9	
65.0	
65.1	
65.2	
65.3	
65.4	
65.5	
65.6	
65.7	
65.8	
65.9	
66.0	
66.1	
66.2	
66.3	
66.4	
66.5	
66.6	
66.7	
66.8	
66.9	
67.0	
67.1	
67.2	
67.3	
67.4	
67.5	
67.6	
67.7	
67.8	
67.9	
68.0	
68.1	
68.2	
68.3	
68.4	
68.5	
68.6	
68.7	
68.8	
68.9	
69.0	
69.1	
69.2	
69.3	
69.4	
69.5	
69.6	
69.7	
69.8	
69.9	
70.0	
70.1	
70.2	
70.3	
70.4	
70.5	
70.6	
70.7	
70.8	
70.9	
71.0	
71.1	
71.2	
71.3	
71.4	
71.5	
71.6	
71.7	
71.8	
71.9	
72.0	
72.1	
72.2	
72.3	
72.4	
72.5	
72.6	


PLANTING BED DETAIL




PLANTING BED




LEVEL SPREADER




STORM MANHOLE




DETENTION OUTLET CONTROL STRUCTURE




EXISTING SIGN



CONCRETE MONOLITHIC SIDEWALK AND CURB




CONCRETE GALLEY DETENTION SYSTEM



CURB CATCH BASIN ("CCB")

-PRECAST-



DEEP TESTS

TESTED ON 5/23/2017 BY RICH BENNET P.E.

TP 11
0"-6" TOPSOIL
6"-72" SILTY SAND WITH BLASTED ROCK (CLEAN FILL)
NO WATER
NO MOTTLING
LEDGE @ 72"

TP 2
0"-4" ASPHALT/GRAVEL
4"-32" SILTY SAND WITH BLASTED ROCK (CLEAN FILL)
NO WATER
NO MOTTLING
LEDGE @ 48"

TP 3
0"-6" TOPSOIL
6"-29" TOPSOIL
NO WATER
NO MOTTLING
LEDGE @ 29"

TP 4
0"-6" TOPSOIL
6"-24" BROWN SILTY LOAM
NO WATER
NO MOTTLING
LEDGE @ 24"

TP 5
0"-6" TOPSOIL
6"-36" CLEAN FILL
36"-48" BLACK ORGANIC
48"-78" CLEAN FILL
NO WATER
NO MOTTLING
NO LEDGE

TP 6
0"-6" TOPSOIL
6"-51" CLEAN FILL (SILTY SAND WITH ROCK)
NO WATER
NO MOTTLING
LEDGE @ 51"

TP 7
0"-6" TOPSOIL
6"-32" CLEAN FILL (SANDY SILT)
32"-66" BLACK ORGANIC
66"-78" CLEAN FILL (SANDY SILT)
NO WATER
MOTTLING @ 32" (PERCHED)
NO LEDGE

TP 8
LEDGE @ 36"

TP 9
0"-18" TOPSOIL/MISC. FILL
18"-44" BROWN SILTY LOAM
WATER @ 44"
NO MOTTLING
LEDGE @ 44"

TP 10
LEDGE @ 28"

TP 11
LEDGE @ 12"

TP 12
LEDGE @ 44"

TP 13
LEDGE @ 46"

TP 14
LEDGE @ 28"

TP 15
LEDGE @ 42"

TP 16
LEDGE @ 76"

TP 17
LEDGE @ 40"

TP 18
LEDGE @ 40"

TP 19
LEDGE @ 40"

TP 20
LEDGE @ 40"

TP 21
LEDGE @ 40"

TP 22
LEDGE @ 40"

TP 23
LEDGE @ 40"

TP 24
LEDGE @ 40"

TP 25
LEDGE @ 40"

TP 26
LEDGE @ 40"

TP 27
LEDGE @ 40"

TP 28
LEDGE @ 40"

TP 29
LEDGE @ 40"

TP 30
LEDGE @ 40"

TP 31
LEDGE @ 40"

TP 32
LEDGE @ 40"

TP 33
LEDGE @ 40"

TP 34
LEDGE @ 40"

TP 35
LEDGE @ 40"

TP 36
LEDGE @ 40"

TP 37
LEDGE @ 40"

TP 38
LEDGE @ 40"

TP 39
LEDGE @ 40"

TP 40
LEDGE @ 40"

TP 41
LEDGE @ 40"

TP 42
LEDGE @ 40"


TP 43
LEDGE @ 40"

TP 44
LEDGE @ 40"

TP 45
LEDGE @ 40"


ACCESSIBLE PARKING STALL DETAIL

PER CT BUILDING CODE AMENDMENT 502.2 TO THE ICC A117.1-2009




MODULAR BLOCK WALL DETAIL

NOT TO SCALE




- NOTES:
- DETAIL IS SHOWN FOR GENERAL CONCEPT OF A GEOSYNTHETIC REINFORCED MODULAR BLOCK RETAINING WALL. CONTRACTOR MAY SUBMIT ALTERNATE WALL CONCEPTS FOR OWNER, ENGINEER, AND/OR CITY APPROVAL.
 - AUGERING INTO THE GEOSYNTHETIC WILL NOT BE PERMITTED.


BOLLARD



TYPICAL PAVEMENT CROSS SECTION



HANDICAP PARKING SIGN



No.	Date	REVISION DESCRIPTION
1.	1/17/2020	PLANNING & ZONING SUBMISSION

BB ENGINEERING

15 Research Drive
Suite 3
Woodbridge, CT 06525
P: (203) 881-8145
www.bbengs.com

Land Surveying, Professional Engineering & Land Use Consultants

CONSTRUCTION DETAILS
AND NOTES
OF
28 HILLPOINT ROAD
WESTPORT, CONNECTICUT

PREPARED FOR
THE CONSERVATIVE SYNAGOGUE
30 HILLPOINT ROAD
WESTPORT, CONNECTICUT 06880

TO THE BEST OF MY KNOWLEDGE AND BELIEF THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON.

Date 1/10/2020

Scale

Job No. 973

Drawing No.

20-01

THIS DOCUMENT, THE IDEAS, AND DESIGN INCORPORATED HEREON IS AN INSTRUMENT OF PROFESSIONAL SERVICE AND THE PROPERTY OF BB ENGINEERING, LLC, AND IS NOT TO BE REPRODUCED OR USED IN WHOLE OR IN PART FOR ANY EXTENSION OF THIS PROJECT OR FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF BB ENGINEERING, LLC.

BRYAN F. NESTERAK, CT. P.E./L.S. 23556